

The SmartView 2 Elevator Unit is a combined audio and visual communication system providing complete ADA compliance within the elevator car. The unit comprises of a display, camera, microphone, and speaker all within one compact housing. The SmartView 2 Elevator Unit also has inputs for the emergency call button and yes / no buttons to allow a trapped passenger to answer text messages that are displayed on the screen. Note: The 7100 Machine Room Unit is required to complete the installation of this unit.



Part #: 7200

Code Compliance:

- Conforms to ASME Standard 17.1, Certified to UL 62368-1

Power Requirements:

- 24vdc (Power Provided by Machine Room Unit)
- **Connections:** Screw Terminals

Wiring Requirements:


- Connect elevator phone and machine room device via PLC on both devices

Optional Connections:

- Compatible with the SmartView Viewing Site
- Connection for an external USB Camera
- Dry contacts for Yes/No or Door Open/Closed buttons and call activation button

Specifications:

Dimensions:	6.28" H x 4.63" W x 0.34" D
Mounting:	Behind the COP Mount
Warranty:	2 Years
Environmental:	32° F to 122° F (0° C to 50° C)
Current Draw:	Active = 0.28A Idle = 0.19A



Back View



Front View



Bottom View



Angled View

Mounting Guide:

